WAREHOUSE W-14, DUBAI INVESTMENTS PARK 2

ELECTRICAL WORKS - BILL OF QUANTITIES (SUPPLY ONLY)

MEP Subcontractor: Sample MEP Services LLC | Ref: DIP-W14-EL-003 | Rev 1

Item	Description	Unit	Qty	Rate
E-01	LV power cable 4 core 50mm2 copper XLPE/SWA/PVC 0.6/1kV	Mtr	140	
E-02	LV power cable 4 core 25mm2 copper XLPE/SWA/PVC	Mtr	220	
E-03	LV power cable 4 core 10mm2 copper XLPE/SWA/PVC	Mtr	310	
E-04	3 core 6mm2 armoured cable for AC units	Mtr	260	
E-05	MCCB 3 pole 160A 36kA	No.	2	
E-06	MCB triple pole 63A C curve	No.	6	
E-07	Distribution board 24 way TPN c/w 100A isolator	No.	2	
E-08	RCCB double pole 40A 30mA	No.	12	
E-09	LED flood light 100W IP65	No.	24	
E-10	LED batten 4ft 36W	No.	90	
E-11	Cable tray perforated HDG 300mm	Mtr	120	
E-12	GI conduit 25mm dia	Mtr	450	
E-13	Expansion anchor bolt M10 x 100	No.	600	
E-14	Flexible cable 3 core 1.5mm2	Mtr	500	
E-15	DP switch 20A with neon for water heaters	No.	8	
E-16	Weatherproof isolator 63A 4 pole IP65	No.	6	
E-17	Copper earth rod 16mm x 2.4m with inspection pit	No.	4	

Rates to include delivery to site. Validity 15 days.